

Report of Survey for Repairs of Engines and Boilers.

No. 56 * 22724
 No. in Reg. Book. Cardiff Date, first Survey Jan^r 30th Last Survey Feb^r 4th 1879
4 on the "Gannetta" S. S. Master W. Geary
 Built at Newcastle-on-Tyne When built 1878
 Tons 899 Owners J. Fenwick & Sons Port belonging to London Classified 100 A 1.

Diameter of Cylinders 31 3/4 Engines made at Newcastle-on-Tyne When made 1878
 Length of Stroke 36"
 Pressure of Steam 80 lbs By whom made Palmers Ship Building Co. Limited.
 Registered Horse Power 110

Particulars of Repairs and Examination On Damage Survey of Propeller Shaft.

Found the inner brass sleeve loose and moved forward 12 1/2" and prevented from moving further forward by the coupling.

Repairs:-

Propeller shaft drawn. the forward and after brass sleeves removed, the parts of shaft where sleeves are fitted turned in the lathe, and new brass sleeves fitted on.

After the Propeller Shaft was re-fitted, the Engines Boilers and Machinery were found in good and satisfactory condition.

The Amount of Fee ... £ 1 : 1 : 0 received by me,
 Certificate (if required) ... £ : : 15/2/ 1879

(Travelling Expenses, if any, £)

Committee's Minute

18

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Lloyd's Register
Foundation

IRON 482-0445

it has since been repaired and
is reported to be in good order.
Submitted that she is eligible
to remain as classed

M
— 3. 3. 79

Santha



© 2019

Lloyd's Register
Foundation