

Report of Survey for Repairs of Engines and Boilers.

No. 83

No. in Reg. Book.

Survey held at Hull on the Iron Screw Steamer "Hartlepool"

Date, first Survey 11th December Last Survey 24th December 1878.

Built at

Tons

557
415

Owners

G. N. Wilkinan

When built

Master

Sharp

Port belonging to

Sunderland

Classed

M. C. 1175

Years assigned

Character in Register Book.

A1
3.78.

Diameter of Cylinders 2: 34 1/2"

Length of Stroke 28"

Pressure of Steam 35 lb per sq. inch.

Registered Horse Power 70.

Engines made at

Sunderland

When made

1865

By whom made

G. Clark.

Particulars of Repairs and Examination

In account of damage now done:
New crankshaft fitted. new forward bearing and crosspiece firmly bolted to bedplate and foundations. New brags for crankpin. connecting rod of forward engine straightened. Piston rod and piston of forward engine taken out and examined in shop. Piston rod straightened. Four studs in the Lever Gudgeon of circulating pump replaced by new ones. New brags guard of airpump piston put in. All working parts of engine examined and adjusted.
In my opinion can remain as classed.

The Amount of Fee ... £ 9 : 9 : — received by me,

Certificate (if required) ... £ 1 : — : — 15th January 1879

(Travelling Expenses, if any, £ —)

Committee's Minute

11th March, 1879

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2019

Lloyd's Register

IRON 483-0185

It is submitted that this
vessel is eligible to remain
as chartered & to have
new machinery certificate
granted from 24th Dec
1878 & to be marked
Lloyd's No. 12 78
Milton 20/1/79



© 2019

Lloyd's Register
Foundation