

REPORT of SURVEY for REPAIRS, &c.

22982
New 24/3/79

No. 3819

No. in Survey held at *Sharpness* Date, first Survey *10th Mar* Last Survey *19th Mar* 1879

Reg. Book.

114 on the *Ship "Airlie"* Master *James Foreman*

TONNAGE under Tonnage Deck

Ditto of Spar Deck, or Awning Deck

Ditto of Poop

Ditto of Raised Qr. Dk.

Ditto of Houses on Deck

Ditto of Forecastle

Gross Tonnage

Crew Space, as per Rule

Register Tonnage, out on Beam

Engine Room

Reg. Tons as St' mers, out on Bm.

Built at *Glasgow*

Owners *S. Bruce & Co.*

Residence

By whom built *Stephen*

Surveyed Afloat & in Dry Dock *For S. S. No 1*

When built

YEAR.

MONTH.

1875

Port belonging to *Sunder*

Destined Voyage *Calcutta*

Length of Poop *15-00* ft. Ditto, Forecastle *15-00* ft. Ditto, Raised Quarter Deck *15-00* ft. Years assigned. Character in Register Book.

Last Survey, No. *20144* Port *Iron* Classed *100 A 1*

2.78

REPAIRS, OR EXAMINATION AS PER RULE

The vessel has been placed in Graving Dock, the hold, keelson, Branks & all loose beiling in bottom lifted for examination of the floors & cement - all fore & aft.

In consequence of Shingle getting below the beiling, the cement was found scratched thin in places more or less all fore & aft & in some parts - the Rivet-heads & Plate were found quite bare but uninjured, such parts have been thoroughly overhauled & re-cemented, floors scraped & coated with one coat white & Red lead mixed, Bottom scraped & coated outside with 2 coats of White Zinc & 1 coat of Zinc & Tallow, Rudder lifted & pushed.

Present Condition of the

Decks

Waterways

Comings

Upper Deck Beams & Fastenings

Lower Deck Beams & Fastenings

Planksheers

Sheerstrakes

Topsides

Wales

Plank (Bottom) and Counter

Engine Room Skylights

General Observations, Opinion as to Class, &c.

Good

Greenails Rivet

Breasthooks and Stemson

Transoms, Pointers, and Crutches

Timbers of the Frame at the openings

Ditto Ditto at other places

Keelsons

Clamps and Shelves

Ceiling

Rudder *Overhauled*

Copper *brass* When put on *Now*

Caulking of

Bottom, Deck, & Waterways

Good

Windlass and Capstan

Pumps

Boats *6*

Masts, Yards, &c.

Condition, how ascertained *On Deck*

Sails *Well found*

Anchors No. of *3 B. 1 S. 2 K*

Cables *270 fathoms*

Hawsers and Warps *Well found*

Standing & Running Rigging *Efficient*

Cargo and Main Hatchways *Good* Hatches *Good*

The Amount of Entry Fee ... £ ... received by me, }

Special ... £ *5: 5: 22nd Mar 1879* }

Certificate (if required) ... £ ...

(Travelling Expenses, if any, £ ...)

Committee's Minute *25th March 1879*

Character assigned *100 A 1*

IRON S. S. No 1

Davidson
Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2019

Lloyd's Register Foundation

IRON 483-0255

(The Surveyors are requested not to write on or below the space for Committee's Minute.)