

23002

~~27999~~

Report of Survey for Repairs of Engines and Boilers.

No.

No. in
Reg. Book.

Survey held at

London

Date, first Survey

Feb 19

Last Survey

26 Feb

1879

890

on the

S. S. "Mazepa"

Master

Built at

Newcastle

When built

1872

Tons

922

Owners

J. H. Wreckton

Port belonging to

London

Classed

Years
assigned.

Character in Register Book.

100A1

Last Survey 22856. Iron

Diameter of Cylinder

31 1/2

Length of Stroke

33

Engines made at

Newcastle

When made

1872

Pressure of Steam

75 lb

Registered Horse Power

190

By whom made

Palmer & Co

Particulars of Repairs and Examination

High pressure cylinder bored out and liner fitted, New Piston fitted with new gunk & new packing rings, Cylinder face trued, Crank shaft examined and found good, Tail shaft drawn and examined & found good, Straps of ligum vitae fitted to after bush where worn down, All sea connections overhauled. The machinery of this vessel appears as far as seen to be in good order and safe working condition, and in my opinion renders the vessel eligible to remain as classed.

The Amount of Fee ... £ 1 : 10

received by me,

Certificate (if required) ... £ :

59/1 1879

(Travelling Expenses, if any, £)

Committee's Minute

18

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2019

Lloyd's Register
Foundation

IRON 483-0286

The. Maching of the vessel. has been
examined owing to vessel grounded,
and is reported to now be in
good condition, submitted
that the vessel is eligible
to remain as classed

MD
5.3.79



© 2019

Lloyd's Register
Foundation