

23268
AIRS, &c
(Rec 28/4/78)

Report handed in and fees applied for 1st April 1899.

Now done on account of damage. Six frames and three veneer frames properly shifted and fitted with bottom pieces. 1 Cheerstrake plate taken off furnace and replaced, 1 Top side plate renewed 1 do furnace and set fair & replaced. and 1 new shell plate renewed being badly damaged 1 shift of lower deck stringer Bar, 4 new shell Bars, 2 new butt straps and 2 Beam Brims straightened. 1 new brooving pipe, a shift of Emergen plank of trunk, about 15 feet long. 1 Forecastle deck plank. 3 Iron Stanchions repaired, and the necessary caulking made good in way of the damages. The Bunkering of trunk overhauled. Soil pipe of stamens closet shifted and repaired. Bottom and keel examined and found in good condition the outside plating coated with patent composition and paint.

Decks	<i>good</i>	Treenails	<i>good</i>	Windlass and Capstan	<i>good</i>
Waterways	<i>do</i>	Breasthooks and Stemson	<i>do</i>	Pumps	<i>good</i>
Comings	<i>do</i>	Transoms, Routers, and Gutches	<i>good</i>	Boats	<i>good</i>
Upper Deck Beams & Fastenings	<i>good</i>	Timbers of the Frame at the openings	<i>do</i>	Masts, Yards, &c.	<i>good</i>
Lower Deck Beams & Fastenings	<i>do</i>	Ditto Ditto at other places	<i>do</i>	Condition, how ascertained	<i>from deck</i>
Plank shears		Keelsons	<i>good</i>	Sails	<i>complete</i>
Sheerstrakes		Stamps and Shelves	<i>good</i>	Anchors	No. of <i>3 B. 10. 2 1/2</i>
Topsides		Ceiling	<i>do</i>	Cables	<i>not fringed</i>
Wales		Rudder	<i>do</i>	Hawsers and Warps	<i>good</i>
Plank (Bottom) and Counter		Copper	<i>✓</i>	Standing & Running Rigging	<i>good</i>
Engine Room Skylights	<i>good</i>	Caulking of			
Coal Bunker, Openings, Lids, &c.	<i>good</i>	Bottom, Deck, & Waterways	<i>good</i>		
General Observations, Opinion as to Class, &c.	<i>This vessel being now in good and efficient condition is in my opinion eligible to remain as classed</i>				

Surveyor to Lloyd's Register of British and Foreign Shipping.

Character assigned

Lloyd's Register
Foundation

Row 434 0123