

# Report of Survey for Repairs of Engines and Boilers.

No. 4855  
 No. in Reg. Book. 98 Survey held at Glasgow Date, first Survey — Last Survey April 20<sup>th</sup> 1879  
 on the S.S. "Behera" late "Lanny David" Master Bathie  
 Built at Newcastle When built 1864  
 Tons 1388.7 Owners W. Lilburn Port belonging to Glasgow Classed — Years assigned. 4.45 Character in Register Book. A.1

Diameter of Cylinder 30" x 52" each Engines made at Newcastle When made 1864  
 Length of Stroke 36" By whom made J. Marshall Compounded 1879-4  
 Pressure of Steam 40lb By M. Paul & Co  
 Registered Horse Power 124 Glasgow

Particulars of Repairs and Examination Engines fitted with new Cylinders, and all pumps pipes & connections made good, Crank Shaft with bearings examined (in the after Pin of this Shaft there is an iron wedge mark (longitudinal) but it is not of a nature to effect the strength of the Shaft to any degree), Stern Tube & Sea connections examined in Dry Dock and new Propeller fitted.

Boilers. New

To conform with the Society's requirements the whole of the Sea Cocks which were fitted on the flat of vessel's bottom have now been removed to the upper turn of the Ribs.

The above alterations and repairs have been satisfactorily completed by M. Paul & Co Glasgow and the Engines & Boilers are now in good working condition and eligible in my opinion to be noted in the Register Book Lloyd's M.C. 4.49

The Amount of Fee ... £ 7 : 0 : 0 received by me, April 29<sup>th</sup>  
 Certificate (if required) ... £ — : — : — April 1879  
 Travelling Expenses, if any, £ 2.2.0

Committee's Minute



The Engines of this vessel have been compounded  
and two new Boilers fitted. Cocks valves &c  
have been fitted in accordance with  
the rules submitted that she is  
eligible to have Lloyd's M.C.  
and a smacking Certificate from  
25<sup>th</sup> April 1879

M 2. 5. 79



© 2019

Lloyd's Register  
Foundation