

2310. 28.03.9

Report of Survey for Repairs of Engines and Boilers.

No. 56 on the S. S. Taunfield Master
No. in Reg. Book. 56 Survey held at London Date, first Survey 3rd April Last Survey April 8th 1878
Built at Newcastle When built 1864
Tons 482 Owners J. Leach & Co. Port belonging to London Classified Years assigned Character in Register Book
765 Last Survey 21300. Iron. Lloyd's No. 7. 77
Diameter of Cylinder 25 1/4 Coups Engines made at Newcastle When made 1877
Length of Stroke 30 By whom made R. W. Hawthorn YEAR. NB 77
Pressure of Steam 75
Registered Horse Power 90

Particulars of Repairs and Examination The port furnace of port boiler was found to be collapsed, owing to an accumulation of dirt on the furnace crown, the defective portion has been cut out and a new plate riveted on, both boilers cleaned and scaled, and defective pipe repaired. The boilers are now in good condition, and in my opinion render the vessel eligible to remain as classed.

No report received in the Hull of ship

This vessel met with an accident to
one of her boilers. It has been repaired,
there being no injury done, no other
part of the machinery was examined
submitted that she is eligible
to remain as cleared

M 29.4.79



© 2019

Lloyd's Register
Foundation