

Report of Survey for Repairs of Engines and Boilers.

No. 4871 Survey held at Bowling & Glasgow Date, first Survey July 25<sup>th</sup> Last Survey May 6<sup>th</sup> 1879  
Book 39 on the S. S. "Orkney" Master

Built at Glasgow When built 1860  
Owners W. Ross & Co Port belonging to Glasgow  
Classed 100 & 11.76  
Years assigned 11.76  
Character in Register Book.

Diameter of Cylinder 30" & 21 1/2" & 30" Engines made at Compounded at Glasgow When made 1864  
Length of Stroke 42" By whom made John & James Thomson  
Pressure of Steam 55 lbs  
Registered Horse Power 200

Particulars of Repairs and Examination Cylinders examined and P. Pistons fitted with new packing rings. Slide Valve Spindles renewed and valves ground up. After length of Crank Shaft new Condenser overhauled and all pumps pipes & valves cleaned and examined Sea Cocks & Valves examined.

Boilers. A considerable number of Screw Stays have been fitted and renewed in the back of Combustion Chambers and fitted with Double Rints, in consequence of the plating being bagged through an accumulation of deposits.

The above repairs have been Satisfactorily Completed by Messrs John & James Thomson and the Engines & Boilers are now in good working condition & eligible in my opinion to be listed in the Register Book Lloyd's M.C. 5.49 for twelve months.

The Amount of Fee ... £ 3 : 3 : received by me, James Morrison  
Certificate (if required) ... £ : : May 1879  
Travelling Expenses, if any, £ 1.0.0

Committee's Minute 18

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Clyde District

Lloyd's Register Foundation

120N484-0409



The Boilers of this vessel have been in a  
defective condition for some time they have now  
been repaired & engines examined & found  
to be in good order it is submitted that she is eligible  
to have Lloyd's M.C. for 12 months  
from 6<sup>th</sup> May - but that this notification  
be not entered in the Register  
Book

15.5.79



© 2019

Lloyd's Register  
Foundation