

Report of Survey for Repairs of Engines and Boilers.

723643

No. 271 on the S. S. Thomas Lea Master
 Reg. Book. Survey held at London Date, first Survey 14th May Last Survey 23rd May 1879
 Built at Newcastle When built 1864
 Tons 406 Owners J. Hurwick & Co Port belonging to London Classified Slips MC 5-78
 Tons 634 Character in Register Book. A 1

Diameter of Cylinder 36 Engines made at London When made 1872
 Length of Stroke 28 By whom made Viet Dock Eng Wks 1878
 Pressure of Steam 35 Registered Horse Power 80

Particulars of Repairs and Examination on account of Damage.

New Crank shaft fitted, new Cylinder covers & studs
 Connecting & piston rods straightened new Bottom
 and Brasses new Bolts and new top & bottom end caps
 fitted. New starting wheel fitted and Discharge pipe
 of donkey and Engine room platform repaired.
 The damage has all now been satisfactorily
 repaired

The safety valves (spring) set under steam to
 35 lbs per square inch.

The machinery of this vessel is now in good order
 and safe working condition and in my opinion
 renders her eligible to have a new Machinery
 certificate granted and Slips MC 5-79 recorded

The Amount of Fee ... 12/6/99 £ 1 : 1 : 0 received by me, J. H.
 Certificate (if required) ... £ 10 : 0 : 0 1879
 (Travelling Expenses, if any, £)

James J. Griffin
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

