

Report of Survey for Repairs of Engines and Boilers.

No. 99 (Rev 30/6/79 10.15)
 No. in Reg. Book. 364 Survey held at Hull Date, first Survey 14th May Last Survey 4th June 1879

on the Iron screw Steamer 'Albatross' Master Henry

Built at Hull When built 1856

Tons 297 Owners H. Lawson Port belonging to Hull Lloyd's M. C. 8.78 Years assigned 5 Character in Register Book 5.78.

Diameter of Cylinder 37 1/2" Engines made at Hull When made 1856

Length of Stroke 30 Pressure of Steam 26 lbs per sq. in By whom made C + N. Earle

Registered Horse Power 90

Particulars of Repairs and Examination of Machinery & Boilers. on putting in and general repairs of Boilers and Docking.

all new tubes. except stay tubes in main Boilers. 128 in each
 new bottoms to combustion chambers. + new pieces in backs of same - as requisite
 22 new screw stays with nuts to bottoms of chambers in each boiler
 15 - " - (9 + 6) in backs of " and new nuts where requisite.
 new furnace bottoms at back ends. Shell lined with 1/4 in plates at back end in steam space. 7 new long stays in steam space in each boiler + 1/2 in doubting plate riveted on front plate of Boiler
 Superheater lined at smoke box end + new plate stays fitted
 Reaming of crank Shaft opened up. + found good.
 A new iron Cap fitted to main bearing. Slide valves & cylinders refaced.
 New bush for propeller shaft fitted to stern tube
 D. Key Engine & Boiler & Steam unchies overhauled.

(Condition of Engines and Boilers, and subsequent Repairs and Examinations, to be clearly stated.)

(The Surveyors are requested not to write on or below the space for Committee's Minute).

The Amount of Fee ... £ 2 : 2 : - received by me, W. G. S.
 Certificate (if required) ... £ - : - : 26th June 1879

(Travelling Expenses, if any, £)

Committee's Minute 18

John B. Stevens.
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

The - Machinery and Boilers of this vessel
have been extensively repaired and
are reported to be in good -
condition. Submitted that she
is eligible to remain as
Classed -

MP 30.6.79



© 2019

Lloyd's Register
Foundation