

23853

11105, &c.
(*Jan 7. 1919*) 11.20

The "Seam Bug" which lacerated ready for her was run into by the Government Steamer "Jag", and sustained damages which necessitated the ship being grounded to prevent her sinking, and being subsequently lifted for examination. The damages by the collision were -

Shear struck on Starboard side, between the second and third reversed frames next before the chain-buck-way, and exactly on a butt of door-plate, stowed in and the back strap of the butt, broken in two, vertically. The door next below plate, that is the second and third plates above port gunwale also cut in two. The reversed frame next before the cut and the single frame next abaft it. Bent inward, and the center in lower waterway broken.

Repairs to this damage have been effected by cutting 2 inches off the fore end of the aftermost damaged plate in shear struck, and renewing the three other plates, with best Gaffers' steel iron of same dimensions as original plates.

Good	Treenails	Good	Windlass and Capstan	Good
do	Breasthooks and Stenson	do	Pumps	do
do	Transoms, Pointers, and Crutches	do	Boats	do
Beams & Fastenings	Timbers of the Frame at the openings	do	Masts, Yards, &c.	do
Beams & Fastenings	Ditto Ditto at other places	do	Condition, how ascertained	see by Carpenter
do	Keelsons	do	Sails	see good suit complete
do	Clamps and Shelves	do	Anchors	No. of 3 B. 1 P. 2 H.
do	Ceiling	do	Cables	see length & size good
do	Rudder	do	Hawsers and Warps	1 new 1 good
do	Copper	When put on	Standing & Running Rigging	do
do	Caulking of			
do	Bottom, Deck, & Waterways			
and Counter				
lights	Coal Bunker, Openings, Lids, &c.	Scuppers	Cargo and Main Hatchways	Hatches
ations, Opinion as to Class, &c.				

damages to this Passes having been efficiently repaired under
Supervision, the is now strong and in good order, and in my opinion
with the confidence of the Committee and should be allowed to
rein her class

(Travelling Expenses, if any, £) £ 17. 0

Character assigned

Character assigned *Barbaphys tomentosus*
See Aid. Memo

July, 1879.

100A
JRW-D

Surveyor to Lloyd's Register of British and Foreign Shipping.

© 2019

Lloyd's Register
Foundation

REN 485-0377

