

Last Survey 19292 Iron 23883

No. 66

Report

Report of Survey for Repairs of Engines and Boilers.

No. 66

Reg. Book. Survey held at Bristol

Date, first Survey Sep-21- Last Survey Feb-21- 1879

4954 on the S S "Marne"

Master R. Fowler

Tons 168
248
210

Owners J. L. Stevens

Port belonging to Plymouth

Classed

Years assigned. Character in Register Book. A

Diameter of Cylinder Two 22"

Length of Stroke 22"

Engines made at Glasgow

When made 1864

Pressure of Steam 40

Registered Horse Power 32

By whom made Canal Basin Foundry Co

Particulars of Repairs and Examination

Cylinder covers removed pistons stripped and examined
Slide valves taken out overhauled and adjusted Crank Shaft brasses
lifted journals examined Propeller Shaft and stern bush examined
Feed pump ram valves and seatings overhauled Roses fitted to
Bilge suction pipes Blow off cock on bottom of ship removed to turn
of bilge above level of stoke hole plates Bilge injection made
non-return Donkey engine bilge suction pipe fitted with non-return
valve All cocks & valves on ship's bottom overhauled and
examined New main Boiler fitted with new safety valves &
mountings complete

On last Survey for completion of the above renewals and
overhauling found Engines & Boiler in good and efficient working
condition under steam

The Amount of Fee ... £ 5 : 5 : 0 received by me,

Certificate (if required) ... £ : : June 6-1879

(Travelling Expenses, if any, £ 2 . 13 . 6)

Committee's Minute

Charles M. Jacobs

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

11th July 1879
Lloyd's Register

2.79

Lloyd's Register
Foundation

This vessel has been fitted with a new
Boiler and had her engine repaired which
was reported on 21st Feb to be in good
working condition. Submitted that she is
eligible to have Lloyd's M.C. and a
certificate from 21st Feb 179 also the
note in the book - N.B. 2.79

ITB *MR* 3.7.39



© 2019

Lloyd's Register
Foundation