

Report of Survey for Repairs of Engines and Boilers.

* 244141

(See 20/8/79)

No. in Book. 26607
 Survey held at Liverpool Date, first Survey 6th July Last Survey 22nd July 1879
 on the "S. S. Elaine" Master Wm. F. Volser
 built at Belfast When built 1869 - 2nd mo
 ons 343 Owners J. H. Lovell & Co Port belonging to Liverpool Classified 90A1
 Character in Register Book. Lloyd's M.C. 8^{mo} 1875

Diameter of Cylinder 5 of 22" 1 of 42" Engines made at Belfast When made 1875
 Length of Stroke 28"
 Pressure of Steam 80 lbs. By whom made B. & J. Coates
 Registered Horse Power 90

Particulars of Repairs and Examination of Engines and Boilers in accordance with the requirements of the Rules for Special Survey No. 2. for Iron Ships. The cylinder covers removed. cylinder pistons and valves examined overhauled and put in good order. Air. Circulating, feed, Bilge pumps and condenser examined and found in good order. Crank shaft opened out examined and found good. Propeller shaft drawn in. relined and a new propeller fitted. All the sea cocks and chests ground and overhauled. The boiler doors removed. The boiler examined through-out cleaned sealed and put in good order. Safety valves examined and found good. Donkey Boiler examined overhauled and put in good order. The machinery and Boilers tested under steam and found satisfactory.

The machinery of this vessel being now in a good and efficient condition. she is in my opinion entitled to retain the notification Lloyd's M.C. (und) and to be marked from this date.

The Amount of Fee ... £ 3 : 3 : received by me, J. F. L.
 Certificate (if required) ... £ : : 19/8 1879

J. G. Kinghorn
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute Liverpool August 19 - 1879

90 A 1. Record Lloyd's M.C. in Red July 1879.

The Making of this vessel - has been
examined at S. S. No. 2. and is reported
to be in good condition, submitted
that she is eligible to remain in
Classed and to have. L. 26 M
C from 22 - July 1879

MD
- 40. 7. 79

[Faint, mostly illegible handwritten text covering the majority of the page, likely bleed-through from the reverse side.]

Marine

26 & 27



© 2019

Lloyd's Register
Foundation