

S.S. "Coluna"
Report of Survey for Repairs of Engines and Boilers.

No. *4998* Survey held at *Bowling & Glasgow* Date, first Survey *Nov 12 2* Last Survey *Dec 3 1899*
Reg. Book. *833* on the *S.S. "City of Gloucester"* Master *H. McHale*
Built at *Montrose* When built *1896-11*
Tons *134* Owners *J. E. Kerr & Co.* Port belonging to *Glasgow* Classified *90-A1*
Lloyd's M.C. 12/99 Years assigned *2 1/2* Character in Register Book. *90-A1*
YEAR.

Diameter of Cylinders *20" x 34"* Engines made at *Glasgow* When made *1898*
Length of Stroke *24"* By whom made *Kemp & Hume*
Pressure of Steam *70 lbs*
Registered Horse Power *55*

Particulars of Repairs and Examination *Engine opened up and all the working parts overhauled and examined Pumps, pipes & Bores examined Sea cocks, valves, Propeller & Sterntube examined on Ship*

Boilers examined throughout, the Lops of the Combustion Chambers which had been brought down by want of water have now been renewed and on the completion of the Repairs an hydraulic pressure was applied of 100 lbs Two new Direct Spring loaded Safety Valves fitted in the place of Lever & Weight and tested under steam to 100 lbs

The above Repairs have been satisfactorily completed by Messrs Hutson & Corbett and the Engines & Boilers are now in good working condition and eligible in my opinion to remain as classed and to be noted in the Register Book Lloyd's M.C. 12/99

Owners wish to have Certificate

The Amount of Fee ... £ *4 : 4 :* received by me *James Morrison*
Certificate (if required) ... £ : : *Dec 1899*
Selling Expenses, if any, £ *1 : 1 : 0*

Committee's Minute
18
James Morrison
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.
Clyde District
Lloyd's Register Foundation

The machinery of this vessel has
been repaired. It is submitted
that she is eligible to
have a new machinery
certificate granted
and Lloyd's Reg. No. 79
recorded
Milton
8/12/79



© 2019

Lloyd's Register
Foundation