

Report of Survey for Repairs of Engines and Boilers.

No. 5047

(Received at London Office, 20/3/40)

No. in Reg. Book. Survey held at

Glasgow

Date, first Survey 8th March Last Survey 13th March 1880

1255 on the Machinery of the

"Corcyra"

(Number of Visits 6)

Tonnage, Gross

179

Built at

Stockton

When built

Year

1862

Ditto, Net

494

Owners

Palgrave Murphy & Co

Port belonging to

Dublin

Diameter of Cylinder

26" x 49"

Engines made by

T. Richardson & Sons, Hartlepool

When made

1876

Length of Stroke

30"

Boilers made by

T. Richardson & Sons, Hartlepool

When made

1876

Pressure of Steam

65 lbs.

If Surveyed Afloat or in Dry Dock Afloat & on the Patent Slip Classed

Years assigned.

Character in Register Book.

A 1

Registered Horse Power

99

Last Survey No.

Port

Particulars of Repairs and Examination

Vessel placed on the Patent Slip

Screw shaft taken out of its place and turned to fit the propeller accurately, new key fitted in screw shaft. new Ligum vite strips fitted in the stern post. Sea connections examined and found in good condition. Cylinders and Slide valves examined and found in good order. Air, feed and bilge pumps found in good order. Crank and Tunnel shafting examined and found sound and in good condition. Main Boiler examined and found much pitted inside on the furnaces, back end tube plates and back plates of combustion chambers. Safety valves tested and loaded to 65 lbs per square inch. Donkey boiler examined and found in good condition, new brass safety valve spindles fitted in the place of the iron spindles and the valves loaded to 40 lbs. per square inch.

General Observations, Opinion, and Recommendation:—

In our opinion the vessel is now in good order and safe working condition, and eligible to have the notification Lloyd's M.C. 3.80. in the Register book but we are of opinion that the boiler should be again surveyed in 12 months from this date.

Entry or Registering Fee

£ " : " : "

Survey Fee ...

£ 3 : 3 : "

received by me,

Certificate (if required) ...

£ " : 2 : 6

March 1880

(Travelling Expenses, if any, £

✓)

Committee's Minute

18

Assigned

James Morrison

J. Stoddart

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Clyde District.

Lloyd's Register Foundation

It is submitted that this
vessel is liable to have
the notification Lloyd's
No. 3. 80 recorded sub-
ject to main Boiler
being examined in
12 months from
that date

M
20/3/85



© 2019

Lloyd's Register
Foundation