

Report of Survey for Repairs of Engines and Boilers.

With ~~2698~~ 26038

(Rev 16/2/80)

No. 59.
No. in Reg. Book. Survey held at Dundee Date, first Survey 22nd Jan Last Survey 26th Jan 1880
17 on the T.S.S. "Queen" Master Sangster
Built at Glasgow When built 1854
Tons 178. Owners W.B. Thompson Port belonging to Dundee Classified - Years assigned. 100 A.1. Character in Register Book. 10.78
271. Lloyd's M.C. 6.76 YEAR.

Diameter of Cylinders 20" & 36" Engines made at Dundee When made 1876
Length of Stroke 22 1/2" Pressure of Steam 65 lbs By whom made W.B. Thompson
Registered Horse Power 58.

Particulars of Repairs and Examination of Engines and Boilers in accordance with the requirements of the Rules for Special Survey.

No. 1. for iron ships

Examined. Cylinders. Valves. Pumps. and Bilge piping. also Crank. and Tunnel shafting. the Condenser has been lifted and rejointed on sole plate. the Tubes taken out cleaned and repacked. all the working parts have been readjusted. and the Bilges cleaned out the outside of vessel has been examined on patent slip. Stern bush. propeller. shaft. and sea cock openings all is now in good working order.

Boiler. examined both out and inside of boiler also furnaces. and Combustion Chamber. found at horizontal seam in back plate. the plate cracked at a number of the rivet-holes. and five bolt patches had been fitted on same. called the Owners attention to this by letter. of which I attach a copy with his reply and remarks on same. otherwise the boiler is in good working order

Exd Safety valves. and Donkey boiler. in good order.

It is respectfully submitted that so far as the boilers and engines of this vessel are concerned. that they be eligible to remain as entered into the Register Book Lloyd's M.C in vol 6.76. for a period not exceeding twelve months from this date. when the boiler should again be submitted for inspection.

The Amount of Fee ... £ 1 : 11 : 6 received by me, }
Certificate (if required) ... £ - : - : - 187 }
(Travelling Expenses, if any, £)

Committee's Minute Friday, December 17th. 1880.

John Sturrock
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.
Dundee

Lloyd's Register
Foundation

IRON 491.0197

It is submitted that this
vessel is eligible to have
the notation *Clas. H.C.*
1880 recorded in the
Register Book, subject
to Border being again
examined in 12
months from Jan
26, 1880
M 16/2/80



© 2019

Lloyd's Register
Foundation

Board of Directors of Lloyd's Register of Shipping and Boilers