

Report of Survey for Repairs of Engines and Boilers.

No. 39172.

(Received at London Office, 15.4.80)

No. in Reg. Book. Survey held at London

Date, first Survey Mar. 13th Last Survey April 8th 1880

144 on the Machinery of the S.S. "Neptuno"

(Number of Visits 5)

Tonnage, Gross 877

Built at Osborne N. Hyllton

When built 1873.

Ditto, Net 555

Owners Latham & Co.

Port belonging to Liverpool

Diameter of Cylinder 28 $\frac{1}{2}$ + 56 $\frac{1}{2}$

Engines made by Blair & Co.

When made 1873.

Length of Stroke 36"

Boilers made by Blair & Co.

When made

Pressure of Steam 65 lbs.

If Surveyed Afloat or in Dry Dock Afloat

Classed

Years assigned.

Character in Register Book.

100A1

Registered Horse Power 130

Lloyd's M.C. 7.79

Last Survey No. 23990 Port Iron

Particulars of Repairs and Examination Examined cylinders which were found to be in good condition. new packing ring fitted to High pressure piston. New bush fitted in stern tube, new tail shaft and new propeller fitted. Examined crank shaft which was in good condition. bearings run up with white metal and shaft well fitted to same. Pistons turned up & piston rings refitted. High pressure piston fitted with new packing ring. cylinders chipped top and bottom of clearance, new neck bushes fitted. glands rebushed and piston rods turned up. New guard fitted to Air pumps bucket. Feed and bilge pump rams turned up and the glands bushed, new brass ball valves fitted to feed pumps. High pressure slide valve rod turned up, new neck bush gland rebushed. Packing under Engine sole plate renewed. Boilers thoroughly cleaned and a few defective rivets in joint circumferential seam renewed. Engines tried under steam and safety valves tested to the working pressure of 65 lbs. per sq. inch

General Observations, Opinion, and Recommendation:— The Engines and Boilers of this ship are in good and efficient condition and are eligible, in my opinion, to remain as classed.

Entry or Registering Fee ... £ — : — :

Survey Fee ... £ 3 : 3 :

Certificate (if required) ... £ : :

(Travelling Expenses, if any, £)

received by me,

11 May 1880

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

Tuesday, May, 11th 1880.

Assigned

Lloyd's Feb 4, 80
J.B.W.



Lloyd's Register Foundation

IRON 492-0289

The Machinery of this vessel has
been repaired and is reported to
be in good condition, submitted
that she is eligible to remain
as classed and have Lloyd's

M.C. 8.4.80

M 12-4-80



© 2019

Lloyd's Register
Foundation