

Report of Survey for Repairs of Engines and Boilers.

(Received at London Office, 18/5/80)

5092

in Survey held at Glasgow Date, first Survey 5th April Last Survey 4th May 1880

on the Machinery of the Screw Steamer "Carfin" (Number of Visits six)

Age, Gross 1190 Built at Glasgow When built 1877

to, Net 766 Owners H. Dixon Port belonging to Glasgow

eter of Cylinders 31" x 54" Engines made by London & Glasgow C^o When made 1877

th of Stroke 36 Boilers made by London & Glasgow C^o When made 1877

ure of Steam 70 lbs. If Surveyed Afloat or in Dry Dock In Dry dock Years assigned 100 Character in Register Book A1

stered Horse Power 150 Classed 100 A1

Survey No. 150 Port Glasgow

Lloyd's M.C. 2.80

Particulars of Repairs and Examination Vessel placed in Graving Dock

Screw shaft drawn in, examined and found in good condition.

Signum Vita in stern bushes renewed where necessary.

Sea connections examined and found in good condition.

The various lengths of tunnel shafting were disconnected and turned round and it was found that they were not bent.

Thrust-blocks found loose on the floor of screw tunnel additional chocks and stays fitted to make it secure.

The tips of two of the propeller blades much broken, a new propeller fitted.

General Observations, Opinion, and Recommendation:— The above repairs having been completed in a satisfactory manner, the machinery of this vessel is now in safe working condition and eligible, in my opinion, to retain her class in the Society's Register Book.

Entry or Registering Fee ... £ 4 : - : -

Survey Fee ... £ 2 : 2 : - received by me, 18th May 1880

Certificate (if required) ... £ - : - : -

(Travelling Expenses, if any, £ -)

A. Stoddart
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute 18

Assigned

Clyde district
Lloyd's Register
Foundation
IRN 492-0348

It is submitted that
this vessel is eligible
to remain as
classified

M.

18/5/88



© 2019

Lloyd's Register
Foundation