

Report of Survey for Repairs of Engines and Boilers.

No. _____ (Received at London Office, 16. 6. 80.)

No. in Reg. Book. Survey held at London Date, first Survey April 15th Last Survey June 10th 1880

on the Machinery of the S. S. "Dacia" (Number of Visits 8)

Tonnage, Gross <u>1856</u>	Built at <u>Sunderland.</u>	When built <u>1867.</u>
Ditto, Net <u>1473</u>	Owners <u>Ind. Rub. Gut Per & Telegraph</u>	Port belonging to <u>London.</u>
Diameter of Cylinder <u>23" + 45"</u>	Engines made by <u>G. Blair</u>	When made <u>1867</u>
Length of Stroke <u>36"</u>	Boilers made by <u>G. Blair</u>	When made <u>1875</u>
Pressure of Steam <u>70 lbs.</u>	If Surveyed Afloat or in Dry Dock <u>Afloat & in Dry Dock</u>	Classed <u>A1</u>
Registered Horse Power <u>170</u>		
Last Survey No. _____	Port _____	

Particulars of Repairs and Examination According to the requirements for Special Survey No 3 for Iron ships.

Cylinders examined and found in good condition. Slide valves examined and found in good order. Examined Air and Circulating pumps which were found to be in good condition. Crank shaft examined and found in good condition. Thrust bearing and tunnel shafting examined and found in good condition. Examined Air and Circulating pumps which were in good condition.

Vessel placed in dry dock all sea cocks examined and overhauled. Propeller disconnected stern bush & stern tube taken out, the tail shaft fitted with brass liners, a new cast iron stern tube fitted and stern bush with lignum vitae. Boilers examined, combustion chambers found to be free from patches, tube plates in good condition, a few seams caulked at bottom.

Examined Safety valves (lever) which were found to be in good condition and afterwards tested under steam, the valves lifting at 70 lbs. per sq. inch.

General Observations, Opinion, and Recommendation:— The Engines and Boilers of this ship being now in good and safe working condition, are eligible in my opinion to be marked in the Register Book with B & M. S. 6. 80

Entry or Registering Fee 6/9⁰⁰ £ 1 : 10 :
 Survey Fee ... £ 5 : 5 : received by me,
 Certificate (if required) ... £ 5 : 10 : 1880

(Travelling Expenses, if any, £)

Committee's Minute Tuesday, September, 7th 1880.

Assigned

Geo. E. Milnerison
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2019

Lloyd's Register
 Foundation

IRON494-0450

The Machinery of this vessel has been
examined at S.S. No. 3 and is reported
to be in good condition. Submitted
that she is eligible to have B.P.M.
£6.80 mounted in the Register
Book.

M 11.6.80



© 2019

Lloyd's Register
Foundation

Report has been received from the Surveyors of Engines and Boilers