

REPORT of SURVEY for REPAIRS, &c.

(Received at London Office, 7/9/80)

14993

o. in Survey held at South Shields

Date, first Survey 5th July

Last Survey 6th July 1880

g. Book. 24 on the S.S. "Usworth"

Master A. Steele

TONNAGE under Tonnage Deck 488

Ditto of Spar Deck, or Avoning Deck

Ditto of Poop

Ditto of Raised Qr. Dk.

Ditto of Houses on Deck

Ditto of Forecastle

Gross Tonnage 547

Crew Space, as per Rule

Register Tonnage, cut on Beam

Engine Room

Reg. Tons as S^rmer, cut on Bm. 346

Built at Newcastle

When built 1869

Owners Gordon & Stamp

Port belonging to London

Residence Sunderland

By whom built Mitchell

Destined Voyage Coasting

If Surveyed Afloat or in Dry Dock H.S. Edwards & Sons Dock

(State Name of Dock)

Length of Poop 22 ft. Ditto, Forecastle

ft. Ditto, Raised Quarter Deck

Years assigned.

Character in Register Book.

Last Survey, No. 25820 Port Iran

Classed

A 1

REPAIRS, OR EXAMINATION AS PER RULE Damage

Cause of Repairs to be clearly stated.

S.S. N^o 3.48

Now done, 1 Plate on starb. Bow renewed, & 3 Butt straps renewed & 4 frames strengthened with doubling bars. The bottom sighted; several batts at the Bilges on each side being rather worn at the outer edges have now been re-caulked and cemented, and the outer surface of shell plating coated with 2 coats of Anglo German Composition up to about 7'6" and one coat of paint above up to about 10 feet.

Present Condition of the

Decks	Good	Freeboards	Good	Windlass and Capstan	
Waterways	"	Breasthooks and Stemson	"	Pumps	Metal
Comings	"	Transoms, Pointers, and Crutches	not seen	Boats	3 R.
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	Good	Masts, Yards, &c.	in when
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	practicable
Planksheers	"	Keelsons	"	Sails	and
Sheerstrakes	"	Clamps and Shelves	"	Anchors	No. of 3 B. 15. 2 K
Topsides	"	Ceiling	"	Cables	not seen
Wales	"	Rudder	"	Hawsers and Warps	Sufficient
Planks (Bottom) and Counter	"	Copper (or P.M.) Cement- When put on	69	Standing & Running Rigging	
Engine Room Skylights	good	Caulking of			
Coal Bunker, Openings, Lids, &c.	good	Bottom, Deck, & Waterways	good		
Scuppers	good				
Cargo and Main Hatchways	good				
Hatches	good				

General Observations, Opinion as to Class, &c.

This vessel is now in good & efficient state of repair & eligible in my opinion to remain as Classed

The Amount of Entry Fee ... £ - : - : - received by me, } W.G.S.
Special ... £ 1 : 1 : - 6th Sep 1880

Certificate (if required) to be sent as per margin... } £ - : - : -

(Travelling Expenses, if any, £ - : - : -)

Committee's Minute

Friday, September 10th 1880

Character assigned

James Libun
Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2019

Lloyd's Register Foundation