

Report of Survey for Repairs of Engines and Boilers.

Dec 8/12/80

No. in Book. *75* Survey held at *Long Kong* Date, first Survey *28/8/80* Last Survey *18/10* 18 *80*
 on the *S.S. Mariveles* Master *Munios*
 Built at *Aberdeen* When built *October 1871*
 Tonnage *359* Owners *Francisco Reyes & Co* Port belonging to *Manila* Years assigned. *80 A 1*
565 Character in Register Book. *2.79*
 Diameter of Cylinder *24 and 46 inches* Engines made at *Aberdeen* When made *1871*
 Length of Stroke *3 feet* Pressure of Steam *60 lbs* By whom made *Hall Russell & Co*
 Registered Horse Power *80*

Particulars of Repairs and Examination *The Engines have been thoroughly overhauled & repaired. The following parts have been renewed, HP Valve Spindle, Bushes & stuffing boxes & glands, crank crassers for after Engine. Valves and seating, to feed & bilge pumps, Bushes to stuffing boxes & glands of ditto. Two Link belocets for LP Valve Spindle. Bushes & stuffing boxes & glands of ditto. Throttle Valve - The propeller has been taken off, Shaft drawn in, Stem bush repaired, and the shaft & propeller replaced, all are now in good condition. Telegraph gear has been overhauled & repaired.*

The Boiler has been thoroughly overhauled and repaired. The following parts have been renewed, Bottom, Back, side plates and stays of Combustion Chamber, Tubes, Back tube plate, Top plate of furnaces, Bridge plates, and dogs for manhole doors. The Boiler has been tested by water pressure at 125 lbs per sq inch and is now in very good condition. The sea cocks have been examined and are all in good condition.

The Engines & Boiler are now in very good Condition and fit for further sea service.

The Amount of Fee *50 dollars* received by me, *Oct 19 1880*
 Certificate (if required) ... £ *10*
 Travelling Expenses, if any, £

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

W. H. Selman
 Marine Surveyor.
 Lloyd's Register
 Inspector of Machinery.

IRON 447-0409

The border of this vessel
appears to have had all the
repairs and the Engineers have
been overhauled

It is submitted that
she is eligible to
remain as
classified

M
11/12/68



© 2019

Lloyd's Register
Foundation