

Palmer Shipbuilding & Iron Co  
 Jarrow on Tyne  
 May 30<sup>th</sup> 1871

# Midship Section of S.S. "Miranda"

Scale 1/2" an inch to one foot

Recd. 2/6/71

and diagonals

Sheer strake doubled with  
 3/4 x 1/16 plate for 1/4 length  
 amidships

## Principle Dimensions

Length at present = 210' 0" } Lengthened 24' 6" = 13' 1" depth.  
 Breadth extreme = 28' 0"  
 Depth of Hold = 17' 9"  
 Flat Girth 29' 5"  
 Depth 19' 25"  
 Flat moulded Breadth = 13' 9"

62.65 x 234.6 = 14,601  
 1569  
 16160

So Class 80 A

Equipment No 16, 160.

Note. The hold beam stringer plate to be attached  
 to outside plating for the vessels length amidships - 140 ft.  
 The Butt straps of the new plating, from bridge  
 upwards, to be 1/2 inch thicker than the plates they  
 connect, & to be riveted.

doubling plate  
 1/2" for 2 length

Note: Additions beyond old scantling  
 shown in red

mm  
 2/6/71



© 2021  
 Lloyd's Register  
 Foundation

IRON 504-0161



1564 Jan

The following is a list of the names of the persons who have been  
 admitted to the office of the Secretary of the Board of Education  
 since the last meeting of the Board, and the date of their admission.  
 The names are given in alphabetical order, and the date of admission  
 is given in parentheses.

