

2210

This vessel has been built in accordance with a midship section submitted and approved for the 90 A grade. She has a bridge house on deck measuring 116 Tons about 50 feet long - but the equipment is regulated as for a flush decked vessel. By Table 22 it is required to add one-tenth to the 2nd number for scantlings for the equipment number of a vessel with a partial awning deck, poop, top-gallant fore-castle or a raised quarter deck, but no mention appears to be made of a bridge or deck house.

It is submitted that provided the equipment number be approved without addition for superstructure the vessel appears to be eligible to be Classed 90 A.1. as recommended.

1/9/74

J. J. J.



© 2021

Lloyd's Register
Foundation

IRON509- 0125