

# S. S. N<sup>o</sup> 70

100 A  
3 decks

SCALE  $\frac{1}{2}$  INCH TO A FOOT

S.S. "Viking"  
Report No. 3885


Rec 4/11/73 & 16/1/74  
AS



Proportions

Length to upper Depth =  $\frac{347.5}{29.3} = 11.86$   
 " to Main Depth =  $\frac{347.5}{21.8} = 15.94$   
 " to Breadth =  $\frac{347.5}{36.8} = 9.43$

Bulkheads 7/16  
 Breadth of head 7 3/4



Lloyds Numerals

Half Girth = 431  
 " Breadth = 18.4  
 Depth = 29.3

Sum-7 = 83.8 Frame numeral }  
 Length = 347.5  
 Product = 29120 Plating numeral }

Equipment numeral 347.5 x 90.8 = 31553

2 Bower Anchors 36 1/2 or 36 1/2

1 Stream " 14  
 1 each Hedge 7 1/2

300 Fathoms 1 1/2 Chain cable  
 90 1 1/2 Stream chain

doubled  
 riveted  
 for 1/2

3 Strakes of plating  
 at bilge trunks riveted  
 for 1/2 length. Straps 1/16  
 Sheerstrake Plating

18m  
 4/11/73

Stem 11' x 2 1/4" x 2 1/4"  
 3/16 x 1 1/2  
 3/11/73

AITKEN & MANSEL  
 SHIPBUILDERS & ENGINEERS  
 GLASGOW



Lloyd's Register  
 Foundation

1R00509-0138