

PLAN OF MASTS FOR

NO 145 S.S.

Masts to be made in three plates in circumference
 Lips of foremast stroke of mast plates to be outside
 as shown on facing
 Butts to be double rivetted below deck all butts above deck
 to be triple rivetted
 Butt Straps to be 1/4" thicker than the plates they connect
 Butt Straps to be fitted outside of masts
 Beams to be double rivetted throughout

3578

Fore Mast

Main Mast

Reck 29-9-75



See Letter
9/10/75

Scale 1/2 inch = one foot

Completed
10/10/75

223 21/9/75