


# Particulars of Masts etc

N<sup>o</sup> 23 ship

Barque "Belle of Arvon" Report No 1143/9


## Fore Mast

Length Overall 70.3  
Housing 20.3  
Length above deck 50.0  
diam at partners 25 1/2 in  
Thickness of plates 5/16 & 5/16  
Butt straps 1/16 thicker than  
plates they connect  
Seams double rivetted  
Butts below partners double  
rivetted remainder table mast  
doubled in way of wedging




## Main Mast

Length Overall 74.0  
Housing 20.0  
Length above deck 54.0  
diam at partners 26 in  
Thickness of plates same  
as fore mast rivets & rivetting  
same as fore mast mast  
doubled in way of wedging





## Bowsprit

Length Overall 38 ft length outside bed 21.0  
diam at bed 28 in  
Thickness of plates 7/16 & 5/16  
Diaphragm plate fitted  
in way of bed also doubled  
in way of bed, Butts inside  
of bed double remainder  
table Butt straps 1/16 thicker  
than plate they connect two  
angles for entire length 3 1/2 + 3 1/2 + 7/16



## Yards

Length Overall 69.0  
diam at centre 17 in  
Thickness of plates 5/16 4/16 3/16  
Seams single Butts overlapped  
& triple rivetted yards doubled at centre



IRON 517-0035