

200 18/5 J

June 18/5 J

Screw Steamer "Ella"  $\frac{443}{692}$  Tons  
 built at Inverkeithing in 1870  
 and classed 90 A.T. Awning Decked  
 (Dimensions 197.5 x 25.3 x  $\frac{11.5}{18.2}$  to main dke  
 to awning dke)

In accordance with circular no 340 the Owner of this vessel submits a load line of 11 feet 11 ins for the approval of the Committee, which load line he states would give a free-board to the top of the awning deck at side of 7 feet.

This freeboard set off on the sketch of Midship section submitted brings the load line level with the main deck, which could not be considered satisfactory. The draught of water given does not correspond with this freeboard measured on the sketch of Midship Section. It is therefore submitted that Mr. Dawkins should be requested to obtain accurate measurements of the vessel, by taking the draught of water amidships and the freeboard (on both sides) from this water line to the upper part of the main deck at the side, and to state whether the vessel has a wood main deck over the iron deck, and if so its thickness.





© 2021

18/5  
18/76

J. H. J.  
H. J.