

Bk Clydebank No 4562

18/6/77

Per 16/6/77

**Midship Section
Barque N^o 26**

to Class 100 A1 at Lloyd's

Half Moulded Girth 32.22
" Breadth 15.98
Depth from top of keel 21.54
69.74

Small N^o Large N^o Outfit N^o
69.74 x 185 = 12901. 13761.

Proportions 8.58 Depths & 5.78 Breadths

poorly 5" less depth.
Poop & Forecastle Deck 5x3

Bulk head plates 6/16 & 5/16 angles 3x3x7/16 30" apart
Rudder Head 4 3/4 Heel 2 3/4
Windlass Main piece 19" Spindle 3 3/8

Side plating of Poop 6/16
" Forecastle 6/16
Bulwarks 1/4

Butt straps of Main deck stringer
sheerstrake & live strake at bulge
1/4 thickened & treble riveted for
1/2 length

Outfit
2 Bower Anchors 25 1/2 cwt ex stock
1 Stream " 21 3/4 " " "
1 Kedge " 10 1/2 " incl "
1 " 5 1/4 " " "
1 " 2 1/4 " " "
270 fathoms 1/8 stud chain Cable
90 " 1/8 Stream " or 10' rope
90 " 5" Hawser
90 " 5" Warp

Barrell, Stenhouse & Co
SHIP BUILDERS

DUNBAR TOWN 5/6/77
St.

Scale 1/2 in - One Foot

