



S.S. "Eclipse." No of report. 3939.

PLAN OF MASTS

Scale 1/2 Inch to one Foot

Masts to be made in three plates in circumference.
Both laps of after plate of mast plates to be outside as shown on drawing.
All seams double rivetted.
All Butts below deck double rivetted.
All Butts above deck to be triple rivetted.
All Butts to be 1/4 inch thicker than the plates they connect.
and to be fitted outside of masts except where marked otherwise.

Rec 14/3/77
46

Fore Mast

11-5"
Rounded 1 1/2-6"
Extreme Length 77-3"

Main Mast

11-0"
Rounded 4 1/4-6"
Extreme Length 70-0"

No 158 SS

120525-0049



Lloyd's Register Foundation