

S. J. Hart  
Report No 3967

Length over all.	243' 9"	Lloyd's
" " " " " "	242' 5"	Length
Breadth extreme.	32' 0"	1/2 Breadth
" " " " " "	31' 10"	" Girth
Depth of Hold.	18' 6"	Depth
Classed 100 A1 at Lloyd's		
119 under 12 Depth.	163 for frames.	68' 5"
74 " 8 Breadth.	" " Plating	16386' 4"
Gross Tonnage about 1385.	" " Equipment	18245' 1"

Rev 17/8/77 & 26/11/77



Spacing of Frames 23 inches  
Keel 8 1/2 x 2 1/2 Stem Post 8 x 5 x 8 at Sep.  
Stem 8 x 2 1/2 x 8 at Sep. Buzzer 5 1/4 x 3 Plates 1/4  
Bulkheads 1/16 Sep 1/16 Tunnel sides 1/16 Top 5/16 of Wood.  
Riveting Stringers in Fore Peak 2 1/2 x 1/16 angle 1 1/2 x 1/16.

No 180

W. GRAY & CO.  
IRON SHIPBUILDERS  
AND  
REPAIRERS  
WEST HARTLEPOOL  
Aug 14 1877

IRON 526-0070