



PLAN OF MASTS

S.S. "Elymène" Report No 4234

Scale $\frac{1}{2}$ Inch to one Foot.

Masts to be made in 3 plates in circumference
Laps of foremast strake of Mast plates to be
Outside as shown on tracing in section
All seams to be double riveted
All bolts below deck double riveted
All bolts above deck to be double riveted
All buttstraps to be $\frac{1}{4}$ inch thicker than the plates they connect
And to be fitted outside of Mast except where marked inside
Position of these bolts to be strictly adhered to
Written dimensions only to be taken

Rev 12/2/79
H

FORE MAST

MAIN MAST

No 170 SS

M.D.
24/2/79

Visit Report 11th Feb 1879
M Davidson



© 2021

Lloyd's Register
Foundation

IRON 535-0152