

Memorandum.

March 11th 1880

From James Laing,
Deptford Yard,
Sunderland.

To Mess^{rs}
Lloyd's Surveyor
Sunderland.

S. S. Grapples.

Fore Mast.

Hoisting	17 feet 4"	}	heel	15 inch diam
hounds	52 feet		deck	19 1/2" d.
top	18 feet 8 inch.		hounds	16 1/2 d.
			Top.	8" diameter.

Plating 5/16"
 above hounds 5/16" & heel 5/16.
 doubling plate in way of deck 10 feet long
 do — do — — 6/16.
 Lap. — — — 3 3/4 inches.
 Rivets — — — 5/8"
 Spaced. — — — 2 1/2" from foot to foot.
 Butt straps 5/16 thicker than plates &
double riveted.

OLG.



© 2021
Lloyd's Register
Foundation