

Length aloft

121/over all

Feet, inches. 139

Extreme Breadth

Feet, inches. 27 4

Depth of H

JER548-0254

On the 25 June 1847 I saw a new Vessel building
 at Deland's House "Lower Yard" then partly in
 frame which appears to be this Vessel and
 I objected to her fore dead wood which was very
 improperly fitted being only mitred at the
 junction of the Keel & Stem and sided one half
 the siding of Keel - I also objected to the
 after dead wood one piece of it being Chestnut
 the frame was rough & badly squared and
 several of the first futtocks were of foreign
 K - Mr. Russell was with me on this
 day and can state whether these objections
 have been removed
 20. Nov. 1848 -

J. H. K. Lane