

Liverpool £13<sup>10</sup>

The following is a statement of the repairs  
done to Ship James & Thomas of Liverpool viz

New Keelson, new hog, new Stenson, new Lower  
deck beams fore & aft, new Stringers —  
new binding fore & aft on the Lower Deck  
new fore main & mizen Mast, new Topmast  
and Lower Yard, Ten new first and Second  
futtock, aft Twenty new third futtock, and top  
timbers new wing Transom new rider across  
the Stern timbers 2 new riders in the lower  
hold across the first and second futtock —  
bolted to the transom and extending 28ft long  
outside plank made new below light water  
mark up to the wales on both sides of 3in  
Quebeck Oak plank Copper fastened to the  
wales — 4 new Streak of wales — and sundry  
other repairs such as new Chain Bobstay  
Bowsprit Shroud Channel luff &c —

Lpool

Wm Dickinson

Shipwright

Lloyd's Register  
Foundation

30 Decr 1834

Shipwright

Foundation

in question within the description