

*Agnis* Liverpool No 1144

We the Undersigned, hereby Certify that in the Month of January Eighteen hundred and Thirty One, we put the Barque "Agnis" into Dock, and gave her 114 new top timbers and third futtocks, New Beams, 5 Inch African Oak plank New blacking Strakes 4½ & 3½ Inch African Oak New topsides 2½ Inch African Oak and new upper Bindings Strakes of 3 Inch African Oak, Transomes, and transom knees all Renewed, part of Stern post and part of Keelson New 4 new Hanks. New keel block timbers - New knees in the upper and lower deck where required - 6 new Beams, new stanchions, gunwale, waterways, and Strakes next the waterways - New counter, and Counter timbers The bottom re-strengthened and every defective plank replaced with new. - The upper plank replaced with new. - The upper deck Bindings, the Transomes and Lower Deck Bindings, the Transomes and Keel, & Keelson all Rebolted. Hanks, Keel, & Keelson all Rebolted. that she was foul'd all over, coppered to the keels, and that she is light, staunch, and sound, in every respect, and fit to carry a cargo of any description on any voyage.

Humble Harry & Willcox

Master Shipbuilders

John Atkin Surveyor for Lloyd's

Lloyd's Register Foundation

Sherpoole  
March 4. 1836

Ranrigd 28 March 1836  
from Carr & Hamilton Liverpool

The Sheer-strokes of African oak good Water-ways of pitch pine