

C. F. SEYFANG, PRINTER, FARRINGDON STREET, LONDON.

Her Masts, Yards, &c. are in good condition, and sufficient in size and length.

She has SAILS.			CABLES, &c.		ANCHORS.	
N ^o .		Fathoms.		Inches.	N ^o .	
2	Fore Sails,	200	Chain	1 3/16	3	Bower, ✓
2	Fore Top Sails,	90	Hempen Stream Cable.....	7/8	1	Stream,
2	Fore Topmast Stay Sails,	90	Hawser	5	1	Kedge,
2	Main Sails,		Towlines			All of proper weight.
2	Main Top Sails,	90	Warp	4		
and is well found			All of <u>good</u> quality.			

Her Standing and Running Rigging is Hemp sufficient in size and good in quality.

She has one Long Boat and two others

The present state of the Windlass is good Capstan good and Rudder good

2 lead Pumps Chambered.

General Remarks—Statement and Date of Repairs.

This is a vessel built of the best Materials is well fastened, shows not the least symptom of motion or decay. is well fastened and in my opinion the rules for a 12 A Ship have been complied with.

Her lower deck clamps are two stakes of 4" African Oak 12 inches wide vertically bolted and their edges keyed together. Her Bilge Planks inside are beveled together and bolted edgewise prior to the outside plank being worked.

at the Present time she has received a new after length

of keel and several planks shifted in the flat of the Bottom in consequence of damage sustained on Her late voyage, has been caulked from keel to gunwale and coppered on Paper to Wales

If Sheathed, Doubled, or Felted, Coppered on Paper to Wales

and Date when last done Feb 7 1839

And I am of opinion this Vessel should be Classed 12 A 1

The Amount of the Fee.....£ 1 : 1 : is received by me, J Bayley

Committee Minute

12 Feb 1839

Character assigned

A 1 for 12 Years



© 2009

Lloyd's Register
Foundation