

LIVS83-0062

Ship "Persia"

This Vessel is about 31 ft. 3 in deep and every Alternate Topstumber from the aft side of Windlass to the Stern only runs the height of the Middle Deck, the spaces between the Topstumbers (above the Middle Deck) vary from 19 inches to 3 feet. & several of the Upper Main Deck Beams are placed in the middle of the spaces making it difficult to place a hanging knee properly. In No. 1 Report the Upper Main Deck is called a "Spar Deck" which seems an incomprehensible term for a Deck under which will be stowed Heavy and Light Dry and Perishable Cargoes as the case may be, and in my opinion ought to have the benefit of every Topstumber run up to the Top Height for its more efficient support.

© 2019

Lloyd's Register  
Maritime

Lloyd's Register  
Serpentine Foundation

*Planksheers*

*Keelsons*

### Clamps and Shelves

## Sails

*Anchors No*

Yards