

"Clara" - 623 tons

Ceiling in the lower hold, at ends of Vessel, "thoroughly rotten"

2 - first futtocks

1 - second do. and { introduced on Port side

8 Chocks

9 Chocks to futtock feet on Starboard side

3 fillings on the Port side

5 do on the Starboard side

The whole of the bilge planks, ceiling planks and timber
strake, towards the ^{after} end of the Vessel, renewed on the
Port side - also some planks new forward, (being
some bilge planks and some below bilge) -
similar repairs on the Starboard side

rough butt end bolts driven where deficient, namely
34 on the Port side and 30 on the Starboard side

Clara,
Between two and three thousand feet of Ceiling planks
were renew'd in the Clara, during the time she was in Dock
last Month, in addition to the Timbers and Chocks &c as reported

The rotten stuff was removed at the time, with the ballast
it has been taken away, with the rubbish. -- I have therefore been unable
to get any part of it, or any sample. -- S. P.

LIV583-0452 (2/2)



© 2021

Lloyd's Register
Foundation

LIV583-0452 (1/2)