

REPORT of SURVEY for REPAIRS.

No. ✓ Port of London Date June 11 1835
 Survey of the Brig Rosehill Master Harrison
 Tonnage 197 By whom built Where built Swansea
 When built 1809 Owners J Benson Port belonging to London
 Destined Voyage
 Surveyed Afloat or in Dry Dock Dry Dock during repairs for damage

Original Survey, No. 91 Dated November 1834
 Port Glasgow Classed R.

Repairs. 18- 1st Futtocks shifted 4 do Cross choeked under the keelson instead of shifting two doubtful. Floors Choeked at Floor & 1st Heads. Several planks shifted outside - being replaced with second-hand oak Plank of good quality - Caulked throughout - and several Bolts shifted in various parts of the Deck fastenings, thoroughly overhauled.

June 12th Sheathing with Weatherstatts Marine Metal over Tarred Paper on Main Bottom

Memor.
Inserted
19 Oct
1835
J.H.B.

General Observations
and Opinion, as
required by the
Instructions

I consider that this Vessel is now in a more efficient condition than she has been for sometime past. The Trunks seen when opened were found to be sound though wainy - I am of opinion that she is in a state of efficient repair and equipment for the conveyance of dry and perishable Cargoes & should be classed R.

George Beatty

The Amount of Fee..... £ 1 : 1 : 0 is received by me.

Committee Minute 17 July 1835

Character assigned Recon Repairs & continue the class

J.H.B.



© 2021

Lloyd's Register
Foundation