

REPORT of SURVEY for REPAIRS.

No. 1677 Port of London Date August 15 1835
 Survey of the Ship Tropic Master Phillips
 Tonnage 369 By whom built _____ Where built London
 When built 1819 Owners Daniel Ho Port belonging to London
 Destined Voyage Barbadoes
 Surveyed Afloat or in Dry Dock Dry Dock during repairs

Original Survey, No. 664 Dated September 25 1834 N. 1
 Port London

Repairs. At the present time 2 lower Stakes of Wale shifted together with all the ~~the~~ Lower Deck Iron Fastenings. 4 After Planks of the Wale on the Larboard side shifted. Wale Toppers and Counters caulked — Copper repaired

General Observations and Opinion, as required by the Instructions.

The Wales and Toppers have been scraped bright and all the fastenings carefully examined and found to be in good condition — The Timbers where seen when opened sound and in good condition — The lower end of the Larboard Side Stern Timber a little decayed & and the end of the Wing Transom to a small extent. These defects have been removed as far as practicable at present and made secure — The Wale Toppers, Decks, Deck fastenings, Breast Hooks, Transoms, Plank sheers, Knight Heads, House Pipes, ^{Copper} and cleatments are all in good order and condition and in my opinion the Ship is entitled to remain clapped N. 1 George Bayley

The Amount of Fee..... £ Proper is received by me.

Committee Minute 21 August 1835

Character assigned N. 1 Class to be continued

Appd

SH



© 2021

Lloyd's Register Foundation