

182.

Annual

# REPORT of SURVEY for REPAIRS.

No. 2682 Survey held at London Date July 19 1836  
 on the Ship Isabella Master A. Brown  
 Tonnage 580 Built at London When built 1818  
 By whom built Marwick Owners Dunbar & Co  
 Port belonging to London Destined Voyage Calcutta  
 If Surveyed Afloat or in Dry Dock Messrs Green & Co Dry Dock

Original Survey, No. 702 Dated 1835 Classed A. 1  
 Port Liverpool

**Repairs.** In Feb'y 1836 at Calcutta in consequence of having been ashore in the Houghly - Stripped caulked from keel to water Tiller, loosed sheathes and Coppered - all the toe Bolts of the upper and Lower Deck knees renewed in the Beams - At the present time caulked from the Copper up - Wale scraped from the Copper up -

At the request of Capt. Brown I enumerated the following repairs stated to have been done at Bombay in 1834 -  
 all new Deck Wale, Topsides, Sheerstrakes, Plank sheers, Stanchions, upper Deck waterway & Spirkettens, 14 Stakes upper Deck clamps, 14 Stake shelf to D<sup>o</sup> - Two Stakes Lower Deck clamps 7" & 8" & two binding stakes 5" thick fore and aft in the hold about the 2<sup>nd</sup> futtock heads - All the in and out Bolts of the upper and Lower Deck knees and binding renewed - has Lower Deck waterway Seal.

General Observations  
 and Opinion, as  
 required by the  
 Instructions.

The frame of the Ship is to be seen from the Lower Deck Clamps about 3 feet down, is square and in good condition - The Beams, knees, waterways, Decks, Beamthorpes & Transoms are all in good condition and the Ship is free from movement upon her fastenings in any part - Her repairs are of that nature & nearly to the extent which is required to restore a Ship to the Character A. but not having been done under the inspection of a Surveyor to the Society she is not in my opinion entitled to the advantage of the vote for restoration.

The Amount of Fee..... £ 3 : 3 : 0 is received by me. Wm

George Bayley

Committee Minute 9 August 1836

Character assigned Need Repairs & continue Class A. 1.

SMS