

3399  
JMA  
40

# REPORT of SURVEY for REPAIRS.

No. 3399 Survey held at London Date June 13<sup>th</sup> 1837  
 on the Rg Milton Master Simon  
 Tonnage 242 Built at Thorne When built 1827  
 By whom built \_\_\_\_\_ Owners G. Birtby  
 Port belonging to London Destined Voyage Stochangel  
 If Surveyed Afloat or in Dry Dock Dry Dock

No. 131 Dated 1835 Classed "B D 1"  
 Original Survey, No. 378 Dated June 10 1836 Reduced Class "B 1"  
 Port of Hull \_\_\_\_\_

### Repairs.

At the present time new (Plank Sheer fore & aft, new Staves & Black Staves from the main rigging to the after part of the fore rigging, one hundred feet of plank shifted in the Topsides of African Oak) new six inch stringer bolts to every alternate timber & dunnage to the Hide Beams, & new Fore piece of Helms of Foreign Oak, Casing repaired, two Iron Riggers from the second Beam to the Apron, all defective trunnels driven out, one new Hide Beam, Caulked from the Keel to the Gunwale and a general overhaul both in Hull & Rigging—

There was a slight indication of dry rot which has been removed having had all the defective parts taken out—

General Observations  
 and Opinion, as  
 required by the  
 Instructions.

Is in a very good state of repair & efficiency, fit for the safe conveyance of dry & perishable Cargoes, and Nam of opinion may be raised to the Class "A, 1"

M. W. D. L. T. O.  
 Surveyor



© 2019

The Amount of Fee..... £ 1 : 1 : - is received by me, JMA  
 Committee Minute 15 1837  
 Character assigned A 1

Lloyd's Register  
 Foundation