

Continuation 3869

REPORT of SURVEY for ~~REPAIRS~~.

No. 3869 Survey held at London Date Oct 14<sup>th</sup> 1837  
 on the Barth Ewing Master Good  
 Tonnage 211 Built at Bristol When built 1828  
 By whom built \_\_\_\_\_ Owners M. J. J. J.  
 Port belonging to London Destined Voyage Salamanca  
 If Surveyed Afloat or in Dry Dock Afloat in West India Dock

Original Survey, No. 3000 Dated 1836 Clap'd 10-41 1835  
 Port London

## Repairs.

Nine Bolts taken out of Upper & Lower Deck for examination  
 and found corroded at heads. Planks through which they passed  
 sound & good. Several Treennails driven out - all good.  
 There is a movement at the hold beams - <sup>to be signale by the</sup> ~~and the~~  
 The Transoms, Breast Hooks, Knight Beams, Knees & other  
 Shelf Beams, knees, Waterways, Plank sheels, Plank outside & in  
 is together with the Timbers of the Frame, Floors & Keelson  
 are sound and in good condition. and the Ship has preserved  
 her original sheer - The Decks & Looming are good.  
 We recommend that the hold beams be wedged - an additional  
 Bolt in wake of every Beam through the transoms & shelf both  
 Upper Deck & hold beams - To put in a pair of long knee Rides to  
 the after hold beam & frame a commission from the ship to the stern - To put in  
 additional Bolts in each Breast Hook & Outlets and  
 a Bolter to each or as before

The Surveyor to state the present Condition of

Upper Deck Fastenings

Spirkettling

Plank Shears

Top-sides

Upper Deck with its Appendages

Lower Deck Fastenings

Walls

Counter

Plank and Treennails  
(Outside to the Water's Edge)

Rudder

Windlass

Capstan

General Observations and Opinion,  
 as required by the Instructions.

Ships Sails Rigging Anchors & Cables good & efficient

In our opinion when the above enumerated  
 fastenings are put in the ship ought to be continued  
 for as long a period as the rules will allow

Surveyed 16-1838 In Dry Dock

The whole of the work recommended is complete the keel appears

Sound &amp; in good condition

The Amount of Fee..... £

Committee Minute

Character assigned

Special

C. F. SEYFANG, PRINTER, FARRINGTON STREET, LONDON.

Lloyd's Register  
 3 Years from 1836

LON 602 - 2106