

# REPORT of SURVEY for REPAIRS.

No. 3936 Survey held at London Date March 2<sup>nd</sup> 1838  
 on the Br. Saint Catherine Master J. Jones  
 Tonnage 197 Built at New Brunswick When built 1827  
 By whom built \_\_\_\_\_ Owners Gordon & Co  
 Port belonging to London Destined Voyage West India  
 If Surveyed Afloat or in Dry Dock in the Ways

Original Survey, No. 607 Port of Liverpool  
1831 Dated 1835 Classed A 1  
 Port of London

**Repairs** At the present time new ceiling boards, & waterway on the  
 the starboard side, two new planks on each side of the  
 deck next the waterway, one new breast hole, one new  
 plank in the ceiling which has been taken out to inspect  
 the timbers, and under, & caulked from the keel upwards,  
 In 1837 had three new bits beams & knees, and new  
 ceiling board & waterway on the starboard side

The Surveyor is also required to state the present Condition of the

Decks <u>Inefficient</u>	Transoms _____	Windlass _____
Upper Deck Beams & Fastenings <u>Very fair</u>	Timbers of the Frame _____	Capstan _____
Lower Deck Beams & Fastenings <u>Satisfactory</u>	Topside _____ <u>Appear</u>	Pumps _____
Spirkettling _____	Wales _____ <u>every</u>	Masts, Yards, &c. _____ <u>Good</u>
Plank Shears _____	Counter _____ <u>fair</u>	Sails _____ <u>Good</u>
Waterways _____	Plank & Treenails (Outside to the Water's Edge) _____ <u>satisfactory</u>	Cables _____ <u>well frayed</u>
Hatchway Comings _____ <u>Good</u>	Rudder _____	Anchors No. of _____
Breasthooks _____	Stoppers _____	Standing & Running Rigging _____

General Observations and Opinion, as required by the Instructions,  
 The Decks of this vessel are very indifferent & thin, defective  
 round the main heads & butto, the ceiling also is  
 a little decayed in places and small appearance  
 of working at the ends of the ribs, in every other  
 respect is in very fair condition & the timbers & keel  
 expressed sound, I am of opinion she is perfectly fit  
 for the conveyance of cargo, not in their ordinary subject  
 to sea damage & should

The Amount of Fee ..... £ 10 : - is received by me, Wm. Lister  
 Committee Minute 8 March 1838  
 Character assigned Admitted to Port of London  
Wm. Lister  
8th March