

Restoration REPORT of SURVEY for REPAIRS.

No. 4355 Survey held at London Date July 31 1838
 on the Ship Royal George Master Richards
 Tonnage 486 Built at Hull When built 1820
 By whom built _____ Owners Arnold Woollett
 Port belonging to London Destined Voyage New South Wales
 If Surveyed Afloat or in Dry Dock Limbrick Dock during the repairs

Original Survey, No. 257/8 Dated 1836 Classed A. 1
 Port London

Repairs At the present time stripped a Strake taken out of the upper course - and opened in all parts as required by the Rule for Restoration -
 New upper piece of stem, Apron. Knight Heads. Horse Pieces knee of the Head - New Low Nelson & Rider, about 40 Top Timbers on each side - New Gallies, Stern & Refastened, Lower Deck Waterways rebolted, Channel work refitted, Planks under both Quarters shifted - 6 Strakes of Ceiling on the Starboard side in the Bidge & 3 on the Starboard side amid ship, and the Ceiling in make of the Beam Bookers -
 All the defective Timbers shifted

The Surveyor is also required to state the present Condition of the

Decks <u>New upper Deck</u>	Transoms <u>New others good</u>	Windlass <u>refitted</u>
Upper Deck Beams & Fastenings <u>11 1/2 New Beams</u>	Timbers of the Frame <u>Good</u>	Capstan <u>Do & New Steps</u>
<u>New W & K and all the H knees refitted</u>	Topsides <u>heavily all new</u>	Pumps <u>Metal Pumps</u>
Lower Deck Beams & Fastenings <u>3 1/2 Beams</u>	Wales <u>about 2/3 shifted</u>	Masts, Yards, &c. <u>Rehauled</u>
<u>317 LK 2 H new & all refastened -</u>	Counter <u>Good</u>	Sails <u>Rehauling</u>
Spirkettling <u>New</u>	Plank & Treennails <u>Good</u>	Cables <u>Good & efficient</u>
Plank Shears <u>New</u>	(Outside to the Water's Edge)	Anchors No. of <u>3. 1. 1</u>
Waterways <u>New Forward & aft - the</u>	Rudder <u>"</u>	Standing & Running Rigging <u>Rehauling</u>
<u>midship pieces of Seats refitted</u>	Copper <u>175 LK & Copper to Wales</u>	
Hatchway Comings <u>New</u>	1838 -	
Breasthooks <u>New & others refitted</u>		

General Observations and Opinion,

as required by the Instructions, All the requisites for restoration having been complied with & the repairs efficiently done, & in opinion that she is eligible for Restoration to A1 for 7 years

George Bayley

The Amount of Fee.....£ 5: 5: - is received by me, W. J. Montague

Committee Minute Certified 1838

Character assigned Restored A1 for 7 years