

Restoration 46444 42 REPORT of SURVEY for REPAIRS.

No. 4444 Survey held at London Date August 11th 1838
 on the Ship Simon Taylor Master Harter
 Tonnage 4371 Built at London When built _____
 By whom built Green & Co Owners Harrison & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Sup.^d King's Dry Dock

Original Survey, No. 283, 288 & 3533 Dated _____ Classed 12/11 now *A.1

Port London

Repairs At the present time for Restoration. New wales, one entire
 stake next under & part of the next - New Blackstake
 Topside. Shearstake. Plank shears. Spirketting. Waterway
 Stake next - One whole Lower Deck beam and two
 half 3^d shifted - One new beam to upper deck and
 two half 3^d. Opened inside at the Bidge - all the
 Channel work refitted - all defective Top timbers
 removed to their original shifts - The upper corner
 plating stripped down as far as the keels of the new timbers
 could be reached - She has been opened and
 examined in conformity with the 1st Rule for Restoration
 The bottom was stripped and resheathed last year when she had new
 upper stem, Apron & Knight Head in 1836

The Surveyor is also required to state the present Condition of the

Decks <u>Good</u>	Transoms <u>Good</u>	Windlass <u>Good</u>
Upper Deck Beams & Fastenings <u>new</u>	Timbers of the Frame <u>"</u>	Capstan _____
Lower Deck Beams & Fastenings <u>new</u>	Topsides <u>new</u>	Pumps _____
Spirketting <u>new</u>	Wales <u>new</u>	Masts, Yards, &c. _____
Plank Shears <u>new</u>	Counter <u>part new</u>	Sails _____
Waterways <u>new</u>	Plank and Treenails <u>Good when seen</u> (Outside to the Water's Edge)	Cables _____
Hatchway Comings <u>Good</u>	Rudder <u>Good</u>	Anchors No. of _____
Breasthooks <u>"</u>	Copper <u>1837</u>	Standing & Running Rigging _____

General Observations and Opinion, We are of opinion that this ship having now
 as required by the Instructions, undergone the requisite repairs for restoration
should be restored A 1 for 8 years from 1837

The Amount of Fee.....£ 5 : 5 : is received by me, George Bayley

Committee Minute 7 Sept 1838

Character assigned Restored to A 1 for 8 years from 1837