

REPORT of SURVEY for REPAIRS.

No. _____ Survey held at 4th Apr Date 5th Apr 1838
on the M "England" Master Coxhead
Tonnage 428 Built at Cherston When built 1813
By whom built _____ Owners J. Ward
Port belonging to London Destined Voyage Mocho
If Surveyed Afloat or in Dry Dock Globe Dock

Original Survey, No. 3083 Dated _____ Classed F1
Port London

Repairs At the present time, the new lower deck beam
^{new} two knees, standards & knees of lower deck partly rotted
wales & strike below doubled with 2 inch African oak
New side counter timber, and counter, new plank in Black
Strike, in way of chain bolts forward, port new Breast
Hook, lining upaired, New pillars to beams, New beamings
^{main} to fore and after hatchways, Deck doubling with ^{1 1/2} inch
deck deals with felt under, and the ship generally overhauled
and sheathed with yellow metal to the bulwarks.
Moorings doubled with 3 inch rope

The Surveyor is also required to state the present Condition of the

Decks <u>filled & double</u>	Transoms <u>good & sound</u>	Windlass <u>good</u>
Upper Deck Beams & Fastenings <u>firm</u>	Timbers of the Frame <u>good</u>	Capstan <u>do</u>
Lower Deck Beams & Fastenings <u>mostly</u> <u>rotted</u>	Topsides <u>good</u>	Pumps <u>do</u>
Spirkettling _____	Wales <u>good fair condition</u>	Masts, Yards, &c. <u>good</u>
Plank Shears _____	Counter <u>doubled new</u>	Sails _____
Waterways <u>good</u>	Plank and Treenails <u>good</u> (Outside to the Water's Edge)	Cables <u>3 chains</u>
Hatchway Comings _____	Rudder <u>good</u>	Anchors No. of <u>4 B & K</u>
Breasthooks _____	Copper <u>good</u>	Standing & Running Rigging <u>good</u>

General Observations and Opinion, The timbers exposed by taking out plank
as required by the Instructions, in the way of fore channels and also the
main transom and counter timbers proved in good
sound condition, the fastenings of upper and lower
deck beams, strops, bows, are ^{now} firm and secure, and the condition
of the ship ^{much} improved

The Amount of Fee.....£ 2 : 2 : is received by me, J. H. P. H. H. H.
Committee Minute 26 Dec 1838
Character assigned Saved & Repaired