

REPORT of SURVEY for REPAIRS.

No. 4703 Survey held at London Date Dec^r 5 1838
 on the Brig A.L. Master Clough
 Tonnage 213 Built at Selby When built 1822
 By whom built _____ Owners Staudring
 Port belonging to Goole Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Church Wharfs

Original Survey, No. _____ Dated May 1838 Classed A.1
 Port Hull

Repairs This vessel has had (in shew last) new Topsides, Blackstrakes, Sheerstrakes & Plankstrakes, all the upper & lower Deck fastenings renewed - together with the plank through which they pass new spirketting. Breast hooks additionally bolted. All new ceiling abaft, & new Hold Beams - a plank of the ceiling on each side above the Bilge taken out app^d for examination - The Timbers are described to have been found good sound - which statement is corroborated by present appearances where they can be seen - Part new Keelson forward) - at the present time on survey recommended to put in a Centre abaft, shift two planks on each side in the ceiling and put in ~~up~~ Hanging knees to Hold Beams -

The Surveyor is also required to state the present Condition of the

Decks <u>Good</u>	Transoms <u>Good</u>	Windlass
Upper Deck Beams & Fastenings <u>new 1838</u>	Timbers of the Frame <u>"</u>	Capstan
Lower Deck Beams & Fastenings <u>do</u>	Topsides <u>new 1838</u>	Pumps
Spirketting <u>do</u>	Wales <u>Good</u>	Masts, Yards, &c. <u>Good & efficient</u>
Plank Shears <u>do</u>	Counter <u>"</u>	Sails
Waterways <u>Good</u>	Plank & Treennails (Outside to the Water's Edge) <u>"</u>	Cables
Hatchway Comings <u>"</u>	Rudder <u>"</u>	Anchors No. of
Breasthooks <u>additionally bolted betw 1838</u>	Copper <u>Single</u>	Standing & Running Rigging

General Observations and Opinion, The Bottom of this vessel presents a very firm and good appearance and in my opinion when the above recommendations are complied with she will be fit for the conveyance of dry and perishable cargo to & from all parts of the world & should be classed A.1
 as required by the Instructions,

The Amount of Fee.....£ : : is received by me,

Committee Minute 6 Dec^r 1838

acter assigned

I have the pleasure, as the Surveyor, to certify that the above work