

# REPORT of SURVEY for REPAIRS.

6698

(726)

No. 40 Survey held at London Date Sept 9 1840  
on the Ship Lady Alda Master Romance  
Tonnage 396 Built at Whitby When built 1837 July  
By whom built Langbourne Owners Daniels & Co  
Port belonging to London Destined Voyage Barbados  
If Surveyed Afloat or in Dry Dock Landed in Dock during repairs

Original Survey, No. Whitby 71, 3874, 4347 Dated 1838 Classed 10 A.1  
0558,  
Port London  
Whitby

**Repairs** At the present time new wing transoms, stern timbers half transom - the after end of the Wales. Topside 4 Planks of Bottom Larboard side & 7 Planks on the Starboard side - Counter - two Breast Hooks taken down and refitted an additional Breast Hook (Iron) & a pair of long knee Rides forward - all new ceiling forward from the keelson to the third Breast Hook forward - ~~Partial~~ Stemson - a shake out on each side inside below the lower Deck hanging knees - a great number of Nails driven out on both sides for examination aloft - a transom put over the heels of the counter timbers secured at each end with a staple knee - several timbers shifted on each quarter - Caulked fore and after Copper up

The Surveyor is also required to state the present Condition of the

Decks	Transoms <u>New Wing &amp; Counter</u>	Windlass
Upper Deck Beams & Fastenings	Timbers of the Frame <u>Good</u>	Capstan
Lower Deck Beams & Fastenings	Topsides	Pumps
Spirkettling	Wales	Masts, Yards, &c.
Plank Shears	Counter	Sails
Waterways	Plank and Treenails (Outside to the Water's Edge)	Cables
Hatchway Comings	Rudder	Anchors No. of
Breasthooks	Copper	Standing & Running Rigging

General Observations and Opinion,  
as required by the Instructions,

The above repair was necessary in consequence partly of premature decay and partly because of imperfect and bad workmanship - The Defects have been carefully examined and ~~it is~~ believed completely removed - In our opinion this is now eligible to remain as classed 10 A.1

The Amount of Fee.....£ 2 : - : is received by me,

Committee's Minute 15th Septe 1840

Character assigned 10 A.1 Record Repair

Repairs £10.10