

REPORT of SURVEY for REPAIRS.

Raising Clap 6924

No. _____ Survey held at London Date Oct 29 to Nov 23 1840
 on the Barge Bramley Master _____
 Tonnage 236 Built at India When built 1801
 By whom built _____ Owners Lawsan
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Free dock

Original Survey, No. 2052, Dated _____ Classed E 1

Port London

REPAIRS

At the present time, Shippers of the Copper, Hump, and Yacht, the Ship and a Caulkess the bottom, unbolts the Channels, makes 2 Strakes of $3\frac{1}{2}$ for doubling & 4 Strakes of African Oak above the original doubling, which runs up to take the Bolt in the Chain plates, which are all new, fitted a new Head Knee, Church's bolster to Caulk the Males, Pinnies and all the, unbolts the Rudder, fitted a new lower knuckle of brace and rebolts the original knuckles - painted the counter with 2^d bit of - fitted the bottom & then sheathed with yellow metal - fitted a Bulk on the Nelson between the fore and main mast, drove out several Bolts in the upper deck frame, and found them in a very poor state - the Mastheads, & Transoms are in a very sound state where they can be seen

Barricades full

Present Condition of the

Ducks	<u>Good</u>	Transoms		Windlass	
Upper Deck Beams & Fastenings	"	Timbers of the Frame	<u>Good where seen</u>	Capstan	
Lower Deck Beams & Fastenings	"	Topsoles	<u>Good</u>	Pumps	<u>None above</u>
Spirkettling	"	Wales	"	Masts, Yards, &c.	<u>good &</u>
Plank Shears	"	Counter	"	Sails	<u>insufficient</u>
Waterways	"	Plank & Treedails (Outside to the Water's Edge)	"	Cables	
Hatchway Coverings	"	Radder	<u>Good</u>	Anchors No. of	
Breasthooks	"	Copper	<u>new</u>	Standing & Running Rigging	<u>overhauling</u>

General Observations and Opinion.

This ship appears in a very efficient state. She has been - thorough over haul, is fit for the safe conveyance of a very considerable cargo. Report upon the parts of the vessel in my opinion may be classed * E

The Amount of Fee.....£ 2. - is received by me, W. H. Clark

Committee's Minute 24th Nov 1840

Character assigned E 1 Antwerp - repair up

Minister 2-2-0

Lloyd's Register
Foundation